HASSAN DIVISION.

Dated 7th June 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 10th July 1928, for constructing a Girder Bridge at 3—15 Manjarabad-Kodlipet Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1929.

2. The plans, detailed estimate specifications and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 12 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of rupees 100 (one hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a girder bridge at 3—15 on Manjarabad-Kodlipet Raod, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate for constructing a girder bridge at 3—15 on Manjarabad-Kodlipet Road :—

No.	Items of work	Unit	Quantity	Remarks
1	Earthwork excavation for foundation ...	C.yds.	184	
2	Filling in foundation in cement concrete ...	C.ft.	1,656	
3	Filling in foundation and basement in stone in cement mortar.	„	2,384	
4	Superstructure with burnt brick in surki mortar ..	„	7,155	
5	Bed slabs 9″ thick for girders laid over cement mortar including 2 line dressing.	S.ft.	24	
6	String course with burnt brick in surki mortar and plastered over.	R.ft.	64	
7	Coping over pedestals with burnt brick in mortar including cornice alround and plastered over.	No.	8	
8	Plastering the masonry walls with surki mortar ...	Sqr.	22·80	
9	Pointing the basement with cement ...	„	5·04	
10	Supplying and hoisting up of 3 girders 10′×5″ over abutments for 13 R.ft. with trough plates and iron railings, etc., including painting.	Lump	sum	
11	Filling in with earthwork for approach road including turfing.	Lump	sum	
12	Lime concrete filling over trough plates ...	C.ft.	98	
13	Mettalling the road including gravelling ..	Lump	sum	
14	Unforeseen charges	„	„	
15	Dismantling the existing bridge	„	„	
16	Baling water from foundations	„	„	

R. L. STEELE,
Executive Engineer.